



NETARHAT RESIDENTIAL SCHOOL
NETARHAT

(An Autonomous Institute under Ministry of School education & literacy Dept ,Govt. of Jharkhand)

NOTICE INVITING SHORT TENDER

Enquiry No- 1001

Dated- 31.05.2016

Sealed Quotations are invited from reputed Parties/Company/Authorized Distributors/Authorized Dealers to construct a partition of room in three parts and Drying & Shocking Yard for Mushroom Project at Netarhat Residential School, Netarhat.

TERMS & CONDITIONS

1. The Quotation should be addressed to the "Principal", Netarhat Residential School, Netarhat, Latehar and should reach on or before 09.06.2016 upto 11.00 a.m. Quotation should be sent through Post/Courier/By hand. The same will be opened at the School campus on 01.00 p.m.
2. Quotations without any erasures and overwriting must be submitted in sealed cover super scribing Enquiry No. and the due date failing which, quotation may be ignored.
3. **Prices-** The rates quoted should be inclusive of all packing, forwarding, transportation sales tax, freight and insurance charges and should remain valid for our acceptance for a minimum period of 60 days from the due date of opening of the quotations. The quotation should be NRS consignee's site basis i.e. Netarhat Residential School, P.O- Netarhat, District- Latehar. No hike/change in prices at any stage after the submission of quotations will be allowed by the School's management.
4. Manufacturer's name of company of origin of the materials offered must be clearly specified. Complete details of illustrated literatures/or drawings, if any, must accompany all quotations.
5. The School will not entertain requests for revision in prices once quoted for whatever reason after the Quotations are opened during the period of contract.
6. **Payment Terms-** 100% Payment will be made within 30 days after successful completion of the work asked in the tender. Triplicate copy of invoices must be submitted along with VAT and Income tax deposition certificate.
7. It should be mentioned specifically whether price quoted includes all taxes and duties. Sales tax and/ or other duties legally intended to be claimed should be distinctly shown in the quotation.
8. **Work Completion-** The Supplier shall complete the work within 15 days from the placement of the Work order. The Work asked in the Tender is tentative; however it may marginally increase/decrease at the time of placing of order.
9. **Documents required-** The Firm/Vendor/Company/Dealer/Distributor has to provide following documents along with the quotation:-
 - a) Registration No. of the Firm/Vendor/Company/Dealership/Distributorship.
 - b) VAT/CST Registration Certificate.
 - c) Income Tax Registration Certificate.
 - d) Authorization form Government agency if any.

- e) Work order if any.
10. The School reserves the right to accept or reject any quotation without assigning any reason thereof. No correspondence in this regard will be entertained.
 11. No quotation will be accepted after the due date and time.
 12. The firm must mention the model number along with brand name, drawing and Picture/Snapshot of the item asked.
 13. The firm have to deposit Rs. 500.00 as a tender fee and Rs. 2000.00 as earnest money deposit (EMD) through in form of Demand draft favoring Principal, Netarhat Residential School payable at SBI Netarhat Branch.

Work &Description

Item No.	Schedule No.	Particulars	Quantity				Unit
			Mushroom Hall	Shocking Yard	Drying Yard	Total Quantity	
01.	5.1.1.	Earth Work in exaction			10.69	10.69	M ³
02.	5.1.10	Clean coarse Sand filling			35.44	35.44	M ³
03.	5.6.1.	Bricks Flat Soling			73.31	73.31	M ²
04.	5.3.2	P.C.C. (1:2:4) with stone chips		1.10	1.78	2.88	M ³
05.	5.2.3.	75 A Brick work (1:6) in found Earth filling (Back filling)			3.90	3.90	M ³
06.	5.1.7	Earth filling (Black filling)			10.69	10.69	M ³
07.	5.2.3	75 A Brick Work (1:6) in found		1.57	7.12	8.69	M ³
08.	5.3.16	25 mm thick DPC (1:2:4)		4.13	8.77	12.90	M ²
09.	5.3.5.1	R.C.C. (1:1.5:3) in foundation			6.22	6.22	M ²
10.	5.5.4	8 mm dia rod	0.02		0.101	0.121	M.T.
11.	5.7.3	12 mm E.P. (1:6) with clean sand	98.99	42.57	93.57	235.13	M ²
12.	5.2.11	150 mm thick cement punning		42.57	93.37	135.94	M ²
13.	Carriage of materials	a) Sand and lead 22 K.M.	11.21	1.73	46.51	59.45	M ³
		b) Bricks and Lead 30 K.M.	2810	637	8306	11753	No.
		c) Stone Chips and Lead 58 KM	0.26	1.10	7.15	8.51	M ³
14.	5.10.7	Dismantling old plastic	70.41	30.17		100.58	M ²
15.	5.10.11	Taking down door choked	1 No.			1No.	Each
16.	5.10.12	Taking down window cheeked	4 No.			4 No.	Each
17.	5.10.10	Taking down door/window shulter	8 No.			8 No.	Each
18.	5.4.1	5/F/F Sal wood in choukhat	0.213			0.213	M ³
19.	5.4.12	5/F/F Sal Wood Panel Shutter	6.336			6.336	M ²
20.	5.4.57.1	3mm thick glass pane	2.51			2.51	M ²
21.	5.5.12	5/F/F M.S. grill	1152.20			1152.20	Kg
22.	5.2.14	75 A Prick Work (1:6) in super space	6.92			6.92	M ³

23.	5.3.7.1	R.C.C. (1:1.5:3) in hard at lintal	0.236			0.236	M ³
24.	5.3.8.1	R,C.C. (1:1.5:3) in lintal	0.64			0.64	M ³
25.	5.5.5	10 mq dia rod	0.012			0.012	M.T.
26.	5.6.19	Kotah Stone Slab flooring	117.26			117.26	M ²
27.	5.6.20	Kotah stone tiles in Dado	9.24			9.24	M ²
28.	5.7.6	6 mm C.P.C. (1:4) in ceiling	29.18			29.18	M ²
29.	5.8.24	Two coats of snowcen new surface	341.12			341.12	M ²
30.	5.8.31	Two coats synthetic enamel pint wooden	93.96			93.96	M ²
31.	5.8.32	Two coats of synthetic enamel paint – steel	41.40			41.40	M ²

Yours Sincerely

Sd/-

Principal

Netarhat Residential School,

Netarhat

Copy to – HOD, Agriculture/Bursar/Accountant/Cashier/ Stores/ School's Notice Board/
Netarhat Bazartand .

Principal

Netarhat Residential School

Netarhat