



**NETARHAT RESIDENTIAL SCHOOL**  
**NETARHAT**

(An Autonomous Institute under Ministry of School education & literacy Dept ,Govt. of Jharkhand)

**VERY SHORT TENDER NOTICE**

Enquiry No- 283

Dated- 15.07.2016

**Sealed Quotations are invited from reputed Parties/Company to construct a Covered Yard for storage of Store Room at Netarhat Residential School, Netarhat.**

**TERMS & CONDITIONS**

1. The Quotation should be addressed to the "Principal", Netarhat Residential School, Netarhat, Latehar and should reach on or before 20.07.2016 up to 11.00 a.m. Quotation should be sent through Post/Courier/By hand. The tender will be opened on 21.07.2016 at the School campus on 11.00 a.m.
2. Quotations without any erasures and overwriting must be submitted in sealed cover super scribing Enquiry No. and the due date failing which, quotation may be ignored.
3. **Prices-** The rates quoted should be inclusive of all packing, forwarding, transportation sales tax, freight and insurance charges and should remain valid for our acceptance for a minimum period of 60 days from the due date of opening of the quotations. The quotation should be NRS consignee's site basis i.e. Netarhat Residential School, P.O- Netarhat, District- Latehar. No hike/change in prices at any stage after the submission of quotations will be allowed by the School's management.
4. Manufacturer's / Supplier's name of company of origin of the materials offered must be clearly specified. Complete details of illustrated literatures/or drawings, if any, must accompany all quotations.
5. The School will not entertain requests for revision in prices once quoted for whatever reason after the Quotations are opened during the period of contract.
6. **Payment Terms-** 100% Payment will be made within 30 days after successful completion of the work asked in the tender. Triplicate copy of invoices must be submitted along with VAT and Income tax deposition certificate. In case the vendor does not provide VAT deposition certificate after billing date the **VAT amount will be deducted as per JVAT rule 2005 section 45.**
7. It should be mentioned specifically whether price quoted includes all taxes and duties. Sales tax and/ or other duties legally intended to be claimed should be distinctly shown in the quotation.
8. **Work Completion-** The Supplier shall start the work within 10 days from the placement of the Work order and should complete the work within 30 days. The Work asked in the Tender is tentative; however it may marginally increase/decrease at the time of placing of order. **If vendor does not complete their work on given time the 1% of the total amount will be deducted per week.**
9. **Documents required-** The Firm/Vendor/Company/Dealer/Distributor has to provide following documents along with the quotation:-
  - a) VAT/CST Registration Certificate should be above commodity .

- b) Income Tax Registration Certificate.
  - c) Authorization from Government agency if any.
  - d) Work order if any.
10. The School reserves the right to accept or reject any quotation without assigning any reason thereof. No correspondence in this regard will be entertained.
  11. No quotation will be accepted after the due date and time.
  12. The firm must mention the model number along with brand name, drawing and Picture/Snapshot of the item asked.
  13. The firm have to deposit Rs. 500.00 as a tender fee through Cash/Demand draft favoring of Principal, Netarhat Residential School payable at SBI Lohardaga Branch.

### **Work &Description**

Item No.	Particulars	Quantity	Unit
01.	Earth Work in excavation in foundation trench in any kind of soil - do-	18.42	M3
02.	Providing coarse Clean Sand filling in foundation in plinth	24.45	M3
03.	Providing 75 A Bricks Flat Soling joints filled with local sand	74.70	M2
04.	Providing R.C.C. (1:1½:3) in foundation with stone chips 20 mm to 6 mm size excluding the cost of reinforcement	3.25	M3
05.	Providing P.C.C.(1:2:4) in foundation with stone chips 20mm to 6 mm size –do-	6.47	M3
06.	Providing 75 A Brick work in C.M. (1:6) in foundation in plinth –do-	5.48	M3
07.	Providing R.C.C (1:1½:3) in Tie beam foundation / plinth with stone chips 20 mm to 6mm excluding the cost of reinforcement	2.36	M3
08.	Providing R.C.C (1:1½:3) in Stiffeners with stone chips 20 mm to 6 mm size excluding the cost of reinforcement	2.39	M3
09.	Providing 75A Brick work in C.M (1:6) in Super structure	17.52	M3
10.	Steelwork- buildup tubular truss including cutting hosting fixing in position and applying a priming cost of steel primer	808	Kg
11.	Supplying G.C.I . sheet Mark TATA Steel 8mm thick roofing	693	Kg
12.	Providing R.C.C ( 1: 1½:3) in bandal Lintal level with stone chips 20 mm to 6mm size excluding the cost of reinforcement	0.96	M3
13.	Providing R.C.C ( 1: 1½:3) in Lintal with stone chips excluding the cost reinforcement	0.22	M3
14.	Providing R.C.C ( 1: 1½:3) in wall beam with stone chips 20mm to 6mm size excluding the cost of reinforcement	1.96	M3
15.	Providing TMT steel rein for equal of 8mm & dia rod as per drawing & design 8mm	0.5736	M.T
	5.5.5 (a) 10mm	0.2824	M.T
	Do (b) 12mm	0.7648	M.T
	Do (c) 16mm	0.2912	M.T
16.	Supplying fitting & fixing good quality well sea sand & well dressed Sal wood in choukhat –door/window	0.136	M3
17.	Supplying fitting & fixing 32mm thick good quality well sea sand & well dressed salwood fully paneled shutter with oxide iron fitting	5.11	M2
18.	Supplying fitting T fixing 150 x 20 x 6 mm type M.S clamp fixing	18	Each

	hole of P.C.I. (1:2:4)		
19.	Supplying fittings fixings M.S. Grill made of 20 X 6 mm M.S. flat – do-	28	Kg
20.	Providing & laying 15 mm – 23 mm thick kotah stone slab flooring over 19 mm thick base of C.M. (1:4)	54.30	M <sup>2</sup>
21.	Providing & laying 25 mm thick kotah stone tiles indado over 12 mm thick cement mortar (1:3)	4.95	M <sup>2</sup>
22.	Labour for fitting & fixing GCI sheet roofing in proper stop with Fastener	80.80	M <sup>2</sup>
23.	Labour for fitting & fixing of GCI sheet ridge including the cost of phastnar	7.20	M <sup>2</sup>
24.	Providing 12 mm thick cement plaster in (1:6) over wale with clear coarsesand.	205.61	M <sup>2</sup>
25.	Providing two coats of snowmen make over a coat of cement premiere new surface	205.61	M <sup>2</sup>
26.	Providing two coats of synthetic enamel paint over a coat of primer and make over new wooden surface	13.59	M <sup>2</sup>
27.	Providing two coats of synthetic enamel paint make over steel surface	12.82	M <sup>2</sup>
28.	Providing primer one coat over steel surface will red lead paint	3.24	M <sup>2</sup>
29.	Making plinth partition 50 mm thik of cement concret over 75 mm thik brick fats soling over 100 mm thik sand filling	19.50	M <sup>2</sup>
30.	Carriage of materials	Sand – 45.28 Bricks – 12470 Stone Chips – 16.24	M <sup>3</sup> Nos. M <sup>3</sup>

**Note : We have got the technical sanction to construct the Covered yard for storage of store room. According to technical sanction the measurement of the yard is 40' X 15' . But we have to contract the yard 30' X 15' due to unavoidable reason.**

**Principal  
Netarhat Residential School,  
Netarhat**

**Copy to – Sri. Ranjan Kumar Singh, HOD, Agriculture Deptt. / Bursar/Accountant/Cashier/ Stores/ School's Notice Board/ Caretaker / Netarhat Bazar tand .**

**Principal  
Netarhat Residential School  
Netarhat**